



- NOTES:**
1. Drawings are to be printed in full colour.
  2. All dimensions in metres unless stated otherwise.
  3. Topographical Survey Reference No: 1600-0922-T dated 23/09/2022 carried out by A.R.M Surveys Ltd was provided by Telford and Wrekin Council.
  4. Utility Services Surveys Drawing No: 21/042\_01 dated 10/08/2021 carried out by M&A Surveys was provided by Telford and Wrekin Council.
  5. All Statutory Undertaker records and the location of assets to be confirmed by Statutory Undertakers/Asset Owners.
  6. All works to be CAT & Genny scanned prior to breaking ground. HSG47 (3rd Edition) & GS6 (4th Edition) guidelines and Amey-HS-Underground Services-CRC-01 - Avoiding and Protecting Underground Services.
  7. Existing chambers and STATS equipment within existing footway to be re-set to suit line and level of proposed footway. Chambers to be set flush with proposed footway level or cycleway level.
  8. Refer to 0200 series drawings for site clearance details.
  9. Refer to 0300 series drawings for fencing details.
  10. Refer to 0700 series drawings for pavement & earthwork details. Also refer to T&WC scheme drawings HOLSNED-TWC-HPV-00-DR-CH-0700 & 0701 for further carriageway information.
  11. Refer to 1100 series drawings for kerbing details.
  12. Refer to 1200 series drawings for signing and lining details.
  13. Refer to 1200 series drawings for traffic signals details.
  14. Refer to 2400 series drawings for structural details.

- KEY:**
- Proposed HB2 kerbs
  - Proposed pedestrian crossings (bullnosed kerb) - 0mm to 6mm upstand
  - Proposed transition kerbs
  - Proposed EF kerbs
  - Proposed buff coloured tactile paving - uncontrolled crossing
  - Proposed red coloured tactile paving - controlled crossing
  - Proposed footway
  - Proposed carriageway re-profiling
  - Proposed 45mm resurfacing
  - Proposed 100mm resurfacing
  - Proposed verge and earthworks construction
  - Proposed timber fence
  - Proposed steel fence
  - Proposed retaining wall works
  - Proposed road markings
  - Proposed traffic signals

Revision	Revision comment	45 & 100mm surfacing key corrected & EF kerb removed from around tactile
C04	Drawn:	GH Date: 05/12/2023
	Checked:	SG Date: 07/12/2023
	Approved:	GG Date: 08/12/2023
Revision	Revision comment	Scheme extent, chainage, earthworks & resurfacing amended
C03	Drawn:	GH Date: 23/11/2023
	Checked:	SG Date: 27/11/2023
	Approved:	GG Date: 27/11/2023
Designed:	MV	Date: 26/05/2023
Drawn:	JD	Date: 26/05/2023
Checked:	DM	Date: 02/06/2023
Approved:	SC	Date: 05/06/2023

Copyright in this design © Amey

**amey consulting**  
www.amey.co.uk



Project Name  
**Holyhead Road Signals**

Drawing Title  
**Proposed General Arrangement  
Sheet 1 of 2**

Project Ref. No: COMHA1T&W029 | Scale: 1:250 @ A1  
Stage: Detailed Design | Dimensions: m

Drawing Number  
Project Number | Originator | Volume  
**COMHA1T&W029 - AMY - GEN**  
**Holyhead Road -DR-CH- 0102**  
Location | Type | Role | Number

Suitability	S4	Suitability Description	For Construction	Revision	C04
-------------	----	-------------------------	------------------	----------	-----

**RESIDUAL DESIGN HAZARDS**  
(The following information has been collected from Preconstruction Information and the Amey CDM Hazard Management Process.)

- 1.4 Roadways (SCHEME WIDE)
- 1.14 Existing Utilities - Demolitions / Excavation for foundations (SCHEME WIDE)
- 1.15 Working close to live traffic, restricted access to works. (SCHEME WIDE)
- 12.1 Traffic signals installation/ Electrical installation works including works within the controller.

Based on Ordnance Survey mapping with the permission of the Controller of H.M. Stationery Office © Crown Copyright. Unauthorised reproduction infringes Crown Copyright and may lead to prosecution or civil proceedings. Telford & Wrekin Council Licence No: 100019694 (2023).